## **DATASHEET - DILER-40-C(115V60HZ)**

Contactor relay, 115V 60 Hz, N/O = Normally open: 4 N/O, Spring-loaded terminals, AC operation



Part no. DILER-40-C(115V60HZ)

Catalog No. 231839

Alternate Catalog XTRMC10A40CX

No.

## **Delivery program**

Delivery program			
Product range			DILER Mini-contactors
Application			Contactor relays
Description			with interlocked opposing contacts
Connection technique			Spring-loaded terminals
Rated operational current			
Conventional free air thermal current, 1 pole			
Open			
at 50 °C	$I_{th} = I_e$	Α	10
AC-15			
220 V 230 V 240 V	I <sub>e</sub>	Α	6
380 V 400 V 415 V	I <sub>e</sub>	Α	3
Contacts			
N/O = Normally open			4 N/O
Code number and version of combination			
Distinctive number			40E
For use with			DILE-C
Actuating voltage			115V 60 Hz
Voltage AC/DC			AC operation
Instructions			Contact numbers to EN 50011 Coil terminal markings to EN 50005

## **Technical data**

#### Conoral

		IEC/EN 60947, EN 60947-5-1, VDE 0660, UL, CSA
Operations	x 10 <sup>6</sup>	10
Operations/h		9000
		Damp heat, constant, to IEC 60068-2-78 Damp heat, cyclic, to IEC 60068-2-30
	°C	-25 - +50
	°C	- 25 - 40
		As required, except vertical with terminals A1/A2 at the bottom
	g	
	g	10
	g	8
		IP20
		Finger and back-of-hand proof
	m	Max. 2000
	kg	0.17
	$\text{mm}^2$	
	·	Operations/h  °C  °C  °C  g  g  g  g  kg

Spring-loaded terminals			
Flexible with or without ferrule DIN 46228		mm <sup>2</sup>	1 x (1 - 2.5)
			2 x (1 - 2.5)
Solid or stranded		AWG	1 x (16 - 14) 2 x (16 - 14)
Stripping length		mm	10
Standard screwdriver		mm	0.6 x 3.5
Contacts			
Interlocked opposing contacts to ZH 1/457, including auxiliary contact module			Yes
Rated impulse withstand voltage	U <sub>imp</sub>	V AC	6000
Overvoltage category/pollution degree			III/3
Rated insulation voltage	Ui	V AC	690
Rated operational voltage	U <sub>e</sub>	V AC	600
Safe isolation to EN 61140			
between coil and auxiliary contacts		V AC	300
between the auxiliary contacts		V AC	300
Rated operational current		Α	
Conventional free air thermal current, 1 pole			
Open			
at 50 °C	$I_{th} = I_e$	Α	10
AC-15			
220 V 230 V 240 V	I <sub>e</sub>	Α	6
380 V 400 V 415 V	le	Α	3
500 V	I <sub>e</sub>	Α	1.5
DC current			
Notes			Switch-on and switch-off conditions based on DC-13, time constant as specified.
DC L/R ≦ 15 ms			
Contacts in series:		Α	
1	24 V	Α	2.5
2	60 V	Α	2.5
3	110 V	Α	1.5
3	220 V	Α	0.5
Control circuit reliability	Failure rate	λ	<10 <sup>-8</sup> , < one failure at 100 million operations
			(at U <sub>e</sub> = 24 V DC, U <sub>min</sub> = 17 V, I <sub>min</sub> = 5.4 mA)
Short-circuit rating without welding			
Maximum overcurrent protective device			
220 V 230 V 240 V		PKZM0	4
380 V 400 V 415 V		PKZM0	4
Short-circuit protection maximum fuse			
500 V		A gG/gL	6
500 V		A fast	10
Current heat loss at I <sub>th</sub>			
AC operated		W	1.1
Magnet systems			
Voltage tolerance			
AC operated			
Single-voltage coil 50 Hz and dual-voltage coil 50 Hz, 60 Hz	Pick-up	x U <sub>c</sub>	0.8 - 1.1
Dual-frequency coil 50/60 Hz	Pick-up	x U <sub>c</sub>	0.85 - 1.1
Power consumption			
AC operation			
Single-voltage coil 60 Hz	Pick-up	VA	25
Single-voltage coil 60 Hz	Sealing	VA	4.6
Single-voltage coil 60 Hz	Sealing	W	1.8
duty factor		% DF	100
Changeover time at 100 % $\mathrm{U}_\mathrm{S}$ (recommended value)			
AC operated closing delay		ms	14 - 21

AC operated With auxiliary contact module Max. closing delay	r	ms	45
Rating data for approved types			
Auxiliary contacts			
Pilot Duty			
AC operated			A600
DC operated			P300
General Use			
AC	\	V	600
AC	,	Α	10
DC	\	V	250
DC	,	Α	0.5

8 - 18

# Design verification as per IEC/EN 61439

AC operated N/O contact opening delay

Design vermodition as per 120/211 01-103			
Technical data for design verification			
Rated operational current for specified heat dissipation	In	Α	6
Heat dissipation per pole, current-dependent	$P_{\text{vid}}$	W	0.4
Equipment heat dissipation, current-dependent	P <sub>vid</sub>	W	0
Static heat dissipation, non-current-dependent	P <sub>vs</sub>	W	1.8
Heat dissipation capacity	P <sub>diss</sub>	W	0
Operating ambient temperature min.		°C	-25
Operating ambient temperature max.		°C	50
IEC/EN 61439 design verification			
10.2 Strength of materials and parts			
10.2.2 Corrosion resistance			Meets the product standard's requirements.
10.2.3.1 Verification of thermal stability of enclosures			Meets the product standard's requirements.
10.2.3.2 Verification of resistance of insulating materials to normal heat			Meets the product standard's requirements.
10.2.3.3 Verification of resistance of insulating materials to abnormal heat and fire due to internal electric effects			Meets the product standard's requirements.
10.2.4 Resistance to ultra-violet (UV) radiation			Meets the product standard's requirements.
10.2.5 Lifting			Does not apply, since the entire switchgear needs to be evaluated.
10.2.6 Mechanical impact			Does not apply, since the entire switchgear needs to be evaluated.
10.2.7 Inscriptions			Meets the product standard's requirements.
10.3 Degree of protection of ASSEMBLIES			Does not apply, since the entire switchgear needs to be evaluated.
10.4 Clearances and creepage distances			Meets the product standard's requirements.
10.5 Protection against electric shock			Does not apply, since the entire switchgear needs to be evaluated.
10.6 Incorporation of switching devices and components			Does not apply, since the entire switchgear needs to be evaluated.
10.7 Internal electrical circuits and connections			Is the panel builder's responsibility.
10.8 Connections for external conductors			Is the panel builder's responsibility.
10.9 Insulation properties			
10.9.2 Power-frequency electric strength			Is the panel builder's responsibility.
10.9.3 Impulse withstand voltage			Is the panel builder's responsibility.
10.9.4 Testing of enclosures made of insulating material			Is the panel builder's responsibility.
10.10 Temperature rise			The panel builder is responsible for the temperature rise calculation. Eaton will provide heat dissipation data for the devices.
10.11 Short-circuit rating			Is the panel builder's responsibility. The specifications for the switchgear must be observed.
10.12 Electromagnetic compatibility			Is the panel builder's responsibility. The specifications for the switch gear must be observed. $\label{eq:specifications}$
10.13 Mechanical function			The device meets the requirements, provided the information in the instruction leaflet (IL) is observed. $\label{eq:continuous}$

## **Technical data ETIM 7.0**

Tooliii da da E i iii 710		
Low-voltage industrial components (EG000017) / Contactor relay (EC000196)		
Electric engineering, automation, process control engineering / Low-voltage switch technology / Contactor (LV) / Contactor relay (ecl@ss10.0.1-27-37-10-01 [AAB716014])		
Rated control supply voltage Us at AC 50HZ	V	0 - 0
Rated control supply voltage Us at AC 60HZ	V	115 - 115

Rated control supply voltage Us at DC	V	0 - 0
Voltage type for actuating		AC
Rated operation current le, 400 V	Α	3
Connection type auxiliary circuit		Spring clamp connection
Mounting method		DIN-rail/screw
Interface		No
Number of auxiliary contacts as normally closed contact		0
Number of auxiliary contacts as normally open contact		4
Number of auxiliary contacts as normally closed contact, delayed switching		0
Number of auxiliary contacts as normally open contact, leading		0
Number of auxiliary contacts as change-over contact		0
With LED indication		No
Manual operation		No